BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

MODIFIED DRAFT SCHEDULE 'B'

Construction of Ward office additional work, Furniture etc in Ward No.05, Byatarayanapura

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. S K KESHAVAMURTHY	
				Rate In figures	Rate In words
1	189.08	Providing and removing centering, shuttering, strutting, propping etc. and Removal of form Work for columns, pillars, piers, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications and directions of Engineer incharge of work, Quantity upto 125%.	Sqm	517.01	Rupees Five Hundred Seventeen And Paise One Only
2	386.10	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. - 0 to 5 mtrs.complete as per specifications and directions of Engineer incharge of work.	Sqm	453.51	Rupees Four Hundred Fifty Three And Paise Fifty One Only
3	13.83	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour complete as per specifications and directions of Engineer incharge of work.	Sqm	856.01	Rupees Eight Hundred Fifty Six And Paise One Only
4	198.55	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications and directions of Engineer incharge of work, Quantity upto 125%.	Sqm	331.06	Rupees Three Hundred Thirty One And Paise Six Only
	14.86	Quantity above 125%.	Sqm	331.06	Rupees Three Hundred Thirty One And Paise Six Only
5	15.24	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	589.57	Rupees Five Hundred Eighty Nine And Paise Fifty Seven Only
	13.60	Quantity above 125%.	Sqm	589.57	Rupees Five Hundred Eighty Nine And Paise Fifty Seven Only
6	21.66	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labour complete as per specifications and directions of Engineer incharge of work.	Sqm	366.21	Rupees Three Hundred Sixty Six And Paise Twenty One Only

Scanned by TapScanner

7	22.00	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated for all works in ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars,posts,struts.butters,string or lacing courses ,parapets,coping,bed blocks,anchor blocks ,plain window cills,fillets including cost of all materials, labour,HOM of machinery, curing,complete as per specifications and directions of Engineer incharge of work, Quantity upto 125%.	Cum	6989.78	Rupees Six Thousand Nine Hundred Eighty Nine And Paise Seventy Eight Only
8	3.65	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated for all works in ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars,posts,struts.butters,string or lacing courses ,parapets,coping,bed blocks,anchor blocks ,plain window cills,fillets including cost of all materials, labour,HOM of machinery, curing,complete as per specifications and directions of Engineer incharge of work. Head Room	Cum	7057.81	Rupees Seven Thousand Fifty Seven And Paise Eighty One Only
9	85.46	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15 cms thick layers and well compacted including vibrating, curing, etc for all super Structure works with all lead and Lift etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed cement for concrete with M-25.complete as per specifications and directions of Engineer incharge of work.	Cum	6232.41	Rupees Six Thousand Two Hundred Thirty Two And Paise Forty One Only
10	16.20	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications and directions of Engineer incharge of work.	Sqm	573.69	Rupees Five Hundred Seventy Three And Paise Sixty Nine Only
11	0.72	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications and directions of Engineer incharge of work. Head Room	Sqm	579.36	Rupees Five Hundred Seventy Nine And Paise Thirty Six Only

Scanned by TapScanner

12	18.36	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of Engineer incharge of work, Quantity upto 125%.	tonne	74723.17	Rupees Seventy Four Thousand Seven Hundred Twenty Three And Paise Seventeen Only
	1.79	Quantity above 125%.	tonne	100808.14	Rupees One lakh Eight Hundred Eight and Fourteen Paise Only
13	0.81	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of Engineer incharge of work. Head Room	tonne	75571.24	Rupees Seventy Five Thousand Five Hundred Seventy One And Paise Twenty Four Only
14	262.24	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications and directions of Engineer incharge of work, Quantity upto 125%.	Sqm	1113.38	Rupees One Thousand One Hundred Thirteen And Paise Thirty Eight Only
15	60.12	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications and directions of Engineer incharge of work. Head Room	Sqm	1153.06	Rupees One Thousand One Hundred Fifty Three And Paise Six Only
16	84.42	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc.,complete as per specifications and directions of Engineer incharge of work.	Sqm	998.86	Rupees Nine Hundred Ninety Eight And Paise Eighty Six Only
17	75.16	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc.,complete as per specifications and directions of Engineer incharge of work. Head Room, Quantity Upto 125%.	Sqm	1038.55	Rupees One Thousand Thirty Eight And Paise Fifty Five Only

Scanned by TapScanner

18	347.89	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	323.13	Rupees Three Hundred Twenty Three And Paise Thirteen Only
	91.51	Quantity above 125%.	Sqm	295.92	Rupees Two Hundred Ninety Five and Ninety Two Paise Only
19	221.99	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of Engineer incharge of work. Head Room, Quantity Upto 125%.	Sqm	336.73	Rupees Three Hundred Thirty Six And Paise Seventy Three Only
20	489.39	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of Engineer incharge of work.	Sqm	244.90	Rupees Two Hundred Forty Four And Paise Ninety Only
21	57.42	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of Engineer incharge of work. Head room	Sqm	251.70	Rupees Two Hundred Fifty One And Paise Seventy Only
22	41.25	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specifications and directions of Engineer incharge of work.	Sqm	246.03	Rupees Two Hundred Forty Six And Paise Three Only
23	392.76	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : including Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of Engineer incharge of work., Quantity upto 125%.	Sqm	268.71	Rupees Two Hundred Sixty Eight And Paise Seventy One Only
24	30.23	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : including Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of Engineer incharge of work. Head Room.	Sqm	275.51	Rupees Two Hundred Seventy Five And Paise Fifty One Only
25	901.08	providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty . Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of alll mateerial cost of labour and scaffolding etc. complete as per specifications and directions of Engineer incharge of work.	Sqm	88.44	Rupees Eighty Eight And Paise Forty Four Only
26	478.09	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and directions of Engineer incharge of work.	Sqm	102.04	Rupees One Hundred Two And Paise Four Only

Scanned by TapScanner

27	422.99	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications page no117 item no 15.49.1 . KSRB 15-14.1 : Extra over Item 15-14.1 for applying oil bound washable distemper on ceiling and / or sloping roofcomplete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	133.79	Rupees One Hundred Thirty Three And Paise Seventy Nine Only
28	326.86	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains,complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	403.63	Rupees Four Hundred Three And Paise Sixty Three Only
29	221.99	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains,complete as per specifications and directions of Engineer incharge of work. Terrace Floor, Quantity Upto 125%.	Sqm	412.70	Rupees Four Hundred Twelve And Paise Seventy Only
30	376.42	Providing and laying M-15 cement concrete flooring, 50 mm thick with metallic concrete hardner topping , under layer of 35mm thick m-15 cement concrete using broken granite metal of 20mm and down size, and top layer 50mm thick of metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with which metallic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement and 1 part of metallic floor hardening compound of approved quality by wt) , including finishing cost of materials, labour, curing,complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	719.95	Rupees Seven Hundred Nineteen And Paise Ninety Five Only
31	29.15	Providing and laying M-15 cement concrete flooring, 50 mm thick with metallic concrete hardner topping , under layer of 35mm thick m-15 cement concrete using broken granite metal of 20mm and down size, and top layer 50mm thick of metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with which metallic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement and 1 part of metallic floor hardening compound of approved quality by wt) , including finishing cost of materials, labour, curing,complete as per specifications and directions of Engineer incharge of work. Head Room.	Sqm	722.22	Rupees Seven Hundred Twenty Two And Paise Twenty Two Only
32	376.56	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm.complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	2329.93	Rupees Two Thousand Three Hundred Twenty Nine And Paise Ninety Three Only

Scanned by TapScanner

33	29.15	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm.complete as per specifications and directions of Engineer incharge of work. Terrace Floor	Sqm	2332.19	Rupees Two Thousand Three Hundred Thirty Two And Paise Nineteen Only
34	18.20	Providing and laying Hassan Green / River Pink granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	5056.68	Rupees Five Thousand Fifty Six And Paise Sixty Eight Only
	3.10	Quantity Above 125%	Sqm	5056.68	Rupees Five Thousand Fifty Six And Paise Sixty Eight Only
35	13.30	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	1376.41	Rupees One Thousand Three Hundred Seventy Six And Paise Forty One Only
36	41.25	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour,complete as per specifications and directions of Engineer incharge of work.	Sqm	1852.60	Rupees One Thousand Eight Hundred Fifty Two And Paise Sixty Only
37	13.30	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	596.37	Rupees Five Hundred Ninety Six And Paise Thirty Seven Only
38	3.75	Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour,complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Nos	1548.75	Rupees One Thousand Five Hundred Forty Eight And Paise Seventy Five Only

Scanned by TapScanner

	0.25	Quantity Above 125%	Nos	1548.75	Rupees One Thousand Five Hundred Forty Eight And Paise Seventy Five Only
39	0.20	Providing Honne wood frames of doors, windows, clerestory windows,ventilators and other frames , wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials, labour, HOM of machineries complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Cum	99324.01	Rupees Ninety Nine Thousand Three Hundred Twenty Four And Paise One Only
	0.04	Quantity Above 125%	Cum	99324.01	Rupees Ninety Nine Thousand Three Hundred Twenty Four And Paise One Only
40	0.15	Providing Teak wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications and directions of Engineer incharge of work.	Cum	181498.41	Rupees One Lakh(s) Eighty One Thousand Four Hundred Ninety Eight And Paise Forty One Only
41	2.36	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	5362.80	Rupees Five Thousand Three Hundred Sixty Two And Paise Eighty Only
	1.60	Quantity Above 125%	Sqm	5353.73	Rupees Five Thousand Three Hundred Fifty Three and Seventy Two Paise Only
42	1.89	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications and directions of Engineer incharge of work. Terrace Floor	Sqm	5362.80	Rupees Five Thousand Three Hundred Sixty Two And Paise Eighty Only
43	3.15	Providing and fixing in position fully panelled Teak wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications and directions of Engineer incharge of work.	Sqm	8106.56	Rupees Eight Thousand One Hundred Six And Paise Fifty Six Only
44	28.50	Providing and fixing 65mmx90mm GRP Doorframe fabricated using E-Glass Chopped Strand Mat (CSM). U.V-stabilized Isopthalic Gelcoat and Isopthalic resin. The thickness of the GRP skin shall not be less than 2.0 mm. The doorframe consists of four segmens, which are provided with plug-in-socket arrangement in-situ in the mould. The segments are plugged in and are joined together by means of screws. The GRP frame shall be provided with wooden reinforcement of 6 locations fro high screw holding capacity for fixing metallic hold fast and shall be consolidated by filling with medium density foam/Plaster with fibre reinforcement. Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat hold fast shall be provided with the frame.complete as per specifications and directions of Engineer incharge of work.	m	519.27	Rupees Five Hundred Nineteen And Paise Twenty Seven Only

Scanned by TapScanner

45	7.88	Providing and fixing factory made single leaf rigid GRP Sandwich composite door shutter of 40 mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and one layer of 450 gns E-Glass Chopped Strand Mat (CSM), impregnated with orthopthalic polyester resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 37mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not lessthan 36mmx32mmand also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc. shall be provided. A structural adhesive compatible with EPS foam shall be used for bonding the core material, the salwood reinforement and the skins. The material and process for manufacturing the door shutters shall confirm to RV-TIFAC Composites Design Centre Standards and specifications and the door shutters tested in confiramation to IS 4020-1994. The finish of shutter will be plain coulur White/IVORY/Beige/Light Grey or any other colour using high quality pigments. Excluding cost of fixtures and	Sqm	4317.45	Rupees Four Thousand Three Hundred Seventeen And Paise Forty Five Only
46	8.36	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Sqm	109.98	Rupees One Hundred Nine And Paise Ninety Eight Only
	0.40	Quantity Above 125%	Sqm	109.98	Rupees One Hundred Nine And Paise Ninety Eight Only
47	48.51	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a	Sqm	5041.94	Rupees Five Thousand Forty One And Paise Ninety Four Only
48	1089.96	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications and directions of Engineer incharge of work, Quantity Upto 125%.	Kg	121.31	Rupees One Hundred Twenty One And Paise Thirty One Only

Scanned by TapScanner

49	87.45	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications and directions of Engineer incharge of work.	Sqm	107.71	Rupees One Hundred Seven And Paise Seventy One Only
50	17.53	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications and directions of Engineer incharge of work.	Sqm	6840.12	Rupees Six Thousand Eight Hundred Forty And Paise Twelve Only
51	10.20	Fabricating, providing and erecting in position Hot dip galvanized Gate. Using 72x72x4.8 mm Sq. G I Pipe Frame with top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanized sq.rod for verticals at 150mm c/c , as shown in the drawing including providing hot do galvanized forged ornamental design in between rods and heads at top, middle and bottom. Intermediate supports of 75x12mm and 50x6mm arch bent to hot dip galvanized flats.The work is inclusive of throughing GI, Flat GI Sqm. rods, placing, welding all the joints including grinding, finishing metal patty, painting two coats enamel painting. The rate is inclusive of all materials Like GI Sq. GI Pipe, GI Forged designs etc., heavy duty hinges are made out of 75mm sold sq. block assembled with 20mm du bearing in three places for each flop. Heavy duty locking arrangement of low places including cost of labour, painting, erection charges using hoist pulley cranes, with all lead and lift, loading, trasportation, unloading, scaffolding charges and all other. complete as per specifications and directions of Engineer	Sqm	13096.29	Rupees Thirteen Thousand Ninety Six And Paise Twenty Nine Only
	1.87	Quantity Above 125%	Sqm	13096.29	Rupees Thirteen Thousand Ninety Six And Paise Twenty Nine Only
52	0.00	Providing & Fixing of Mineral Fibre Suspended Ceiling System in the module size of 600x600x19mm with exposed grid. The tiles should have Humidity Resistance(RH) of 99%, Light Reflectance 87%, Thermal conductivity k=0.052-0.057w/m K,NRC-0.7, colour white, Fire Performance UK A2 S1, do with antimicrobial coating on the face of the tile, suitable for zone 4 area according to NF S 90-35:2003 with clean room clss of ISO 5(class 100), Decontamination class of CP10 and Bactoriological cleanlines class B1 for specific strains and reduction in colony size. Washability properties of 500 wash cycles as per ASTM D-4828 and suitable for Green Building application with Recycled content of 37%. The tile shall be laid on 24mm wide T-section flanges colour white having rotary stitching on all t sections i.e. the main runner, 1200mm & 600mm cross tees with web height f 38mm and a load carrying sections should have a galvanizing of 90grmas per sqm and need to be installed with suspension system of approved makecomplete as per specifications and directions of Engineer incharge of work.	Sqm	2816.32	Rupees Two Thousand Eight Hundred Sixteen And Paise Thirty Two Only

Scanned by TapScanner

Sl. No.						
	53	0.00	Providing and fixing veneer paneling over the 50mm x 35mm sal wood frame work at spacing not exceeding 600mm c/c fixed to the wall and top covered out of 4mm thick approved veneer fixed over 12mm ply of approved brand ,termite and water resistant,finished with mealamme polish, complete including cost and conveyance of all materials, labour for all items of work HOM of equipment etc., complete as per specifications and directions of Engineer incharge of work.	Sqm	4239.22	Rupees Four Thousand Two Hundred Thirty Nine And Paise Twenty Two Only
	54	0.00	Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding for straight Brick/Rcc/stone walls & coloumns/beams with necessary aluminium frame works at required level made out of 50x25x3mm C section or equalent. The panel should consist of 2.5 mm thermoplastic core of antitoxic LDPE sandwiched between 0.25 skins thick aluminium sheet making a total panel thickness of 3mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessary accessories, sealing shall be done using weather sealant of Dow Corning 789 with necessary rods etc., complete as per specifications and directions of Engineer incharge of work.	Sqm	4988.65	Rupees Four Thousand Nine Hundred Eighty Eight And Paise Sixty Five Only
	55	0.00	Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding for straight Brick/Rcc/stone walls & coloumns/beams with necessary aluminium frame works at required level made out of 50x25x3mm C section or equalent. The panel should consist of 2.5 mm thermoplastic core of antitoxic LDPE sandwiched between 0.25 skins thick aluminium sheet making a total panel thickness of 3mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessary accessories, sealing shall be done using weather sealant of Dow Corning 789 with necessary rods etc., complete as per specifications and directions of Engineer incharge of work. First Floor	Sqm	4995.45	Rupees Four Thousand Nine Hundred Ninety Five And Paise Forty Five Only
	56	0.00	Providing and fixing of Aluminium composite panel of approved make and colour for wall cladding for straight Brick/Rcc/stone walls & coloumns/beams with necessary aluminium frame works at required level made out of 50x25x3mm C section or equalent. The panel should consist of 2.5 mm thermoplastic core of antitoxic LDPE sandwiched between 0.25 skins thick aluminium sheet making a total panel thickness of 3mm. The surfaces will be finished with PVDF based coating on topsides and service coating on reverse sides would be in polyester paint. The system shall be fixed using GI brackets, aluminium L cleats and stainless steel bolts and nuts complete with spring washer and cap nuts and all other necessary accessories, sealing shall be done using weather sealant of Dow Corning 789 with necessary rods etc., complete as per specifications and directions of Engineer incharge of work. Second Floor	Sqm	5002.26	Rupees Five Thousand Two And Paise Twenty Six Only

Scanned by TapScanner

57	0.00	Providing, fabricating and fixing of stick type structural glazing using Alluminium Extrusions of 63.5 mm x 58.00 mmx 2.25 mm of 1.73 kgs/ mtr for vertical and Horizontal members and 63.5 mm x 38.1 x 1.33 mm of 0.759 kg/Mtr, as outer frame with Electro Anodized Paint coated block finishing, using 6mm thick imported glass reflective hard coatedocean blue raw glass with all necessary accesories like ultra glass Silicon sealant of Space tape, Masking tape, Galvanized Anchaor bolt, machine screws, 6mm thick M.S. angle 50mm x 150mm x 6mm M.S. Galvanized L Brackets, structural sealent setting clocks, fasteners, wall connection etc., complete as per specifications and directions of Engineer incharge of work.	Sqm	7543.06	Rupees Seven Thousand Five Hundred Forty Three And Paise Six Only
58	0.00	Providing, fabricating and fixing of stick type structural glazing using Alluminium Extrusions of 63.5 mm x 58.00 mmx 2.25 mm of 1.73 kgs/ mtr for vertical and Horizontal members and 63.5 mm x 38.1 x 1.33 mm of 0.759 kg/Mtr, as outer frame with Electro Anodized Paint coated block finishing, using 6mm thick imported glass reflective hard coatedocean blue raw glass with all necessary accesories like ultra glass Silicon sealant of Space tape, Masking tape, Galvanized Anchaor bolt, machine screws, 6mm thick M.S. angle 50mm x 150mm x 6mm M.S. Galvanized L Brackets, structural sealent setting clocks, fasteners, wall connection etc., complete as per specifications and directions of Engineer incharge of work. First Floor	Sqm	7549.87	Rupees Seven Thousand Five Hundred Forty Nine And Paise Eighty Seven Only
59	0.00	Providing, fabricating and fixing of stick type structural glazing using Alluminium Extrusions of 63.5 mm x 58.00 mmx 2.25 mm of 1.73 kgs/ mtr for vertical and Horizontal members and 63.5 mm x 38.1 x 1.33 mm of 0.759 kg/Mtr, as outer frame with Electro Anodized Paint coated block finishing, using 6mm thick imported glass reflective hard coatedocean blue raw glass with all necessary accesories like ultra glass Silicon sealant of Space tape, Masking tape, Galvanized Anchaor bolt, machine screws, 6mm thick M.S. angle 50mm x 150mm x 6mm M.S. Galvanized L Brackets, structural sealent setting clocks, fasteners, wall connection etc., complete as per specifications and directions of Engineer incharge of work. Second Floor	Sqm	7556.67	Rupees Seven Thousand Five Hundred Fifty Six And Paise Sixty Seven Only
E1	157.19	Pg No 43,Item No 7.29 Fabrication supplying and erecting M.S. tubular trusses of all spans with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the. members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, letc., complete as per specification	kg	125.85	Rupees One Hundred Twenty Five and Eighty Five Paise Only

Scanned by TapScanner

E2	37.63	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.Pg No.299 Item No.38.30	Sqm	780.04	Rupees Seven Hundred Eighty and Four Paise Only
E3	96.43	Fabricating, providing and erecting in position of MS. Hot dip galvanized Sq Hallow Poles of 132*132 Heavy gauge of length 3000mm with MS. Hot dip galvanized grill work as per approved design and drawing of chief architect. Using 12*65mm galvanized flat for alround frame and 20mm*20mm galvanized forged design with square for vertical at 150mm C/C as shown in the drawing including providing forged omamenttal arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placiing welding all the joints, including grinding, finishing 2 coats of anti corrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS Hallow galvanized pipe, flat, forged square rods, coat of labour for all items of work cost painting, welding, Cutting, grinding with all lead and lift as per specification including loading with cost and conveyance of all materials, labour machinery and incidental charges for the successful complete of the work as per the direction Engineer-in-charge of the work.	Sqm	16408.37	Rupees Sixteen Thousand Four Hundred Eight and Thirty Seven Paise Only
E4	6.09	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer including cost of materials ,labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Sqm	7578.82	Rupees Seven Thousand Five Hundred Seventy Eight and Eighty Two Paise Only
E5	24.16	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work In all kinds of soils Depth upto 3 m as per the direction of Engineer-In-Charge	Cum	84.30	Rupees Eighty Four and Thirty Paise Only
E6	4.83	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates	Cum	6614.58	Rupees Six Thousand Six Hundred Fourteen and Fifty Eight Paise Only

Scanned by TapScanner

E7	43.09	Providing and laying in position Reinforced cement concrete for all Sub tructures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite /trap /basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates	Cum	6790.11	Rupees Six Thousand Seven Hundred Ninety and Eleven Paise Only
E8	32.89	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6180.38	Rupees Six Thousand One Hundred Eighty and Thirty Eight Paise Only
E9	24.16	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/ Kankar /Moorum. (Tipper 5.5 m3)	Cum	136.26	Rupees One Hundred Thirty Six and Twenty Six Paise Only
E10	30.92	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	Cum	110.86	Rupees One Hundred Ten and Eighty Six Paise Only

Executive Engineer
Yelahanka Project Division
BBMP

Scanned by TapScanner